

PROJECT PROPOSAL & COST ESTIMATE

Date: June 9, 2026

Project Title: Supply, Delivery, Installation, and Commissioning of an IP-Based CCTV Surveillance System

Client: ONE LIFE

System Architecture: High-Definition IP Surveillance (16 Active Video Channels)

Hardware Ecosystem: DAHUA Network Solutions

I. HARDWARE & PERIPHERALS (30% Contractor Markup Applied)

All hardware items are commercial-grade Dahua IP network models with integrated Power-over-Ethernet (PoE).

Description	Qty	Unit	Unit Price (PHP) (With 30% Markup)	Total Price (PHP)
Dahua 16-Channel 4K Network Video Recorder (NVR)	1	pc	₱16,900.00	₱16,900.00
6TB Surveillance Hard Drive (WD Purple / SkyHawk)	1	pc	₱24,700.00	₱24,700.00
Dahua 4MP IP Dome Cameras (Indoor zones)	12	pcs	₱6,500.00	₱78,000.00
Dahua 4MP IP Bullet Cameras (Perimeters/Corridors)	4	pcs	₱5,980.00	₱23,920.00
Dahua 24-Port Gigabit Network Switch PoE	1	pc	₱31,200.00	₱31,200.00

Description	Qty	Unit	Unit Price (PHP) (With 30% Markup)	Total Price (PHP)
6U Wall Mount Data Cabinet with lockable safety door	1	pc	₱6,500.00	₱6,500.00
1KVA Uninterruptible Power Supply (UPS)	1	pc	₱6,500.00	₱6,500.00
24" LED Monitor (Stationed at main DVR station)	1	pc	₱9,100.00	₱9,100.00
SUBTOTAL — HARDWARE & ENCLOSURES				₱196,820.00

II. STRUCTURED CABLING & CONDUIT CONTAINMENT (30% Markup Applied)

Itemized pipeline infrastructure based on the 23.11m x 11.32m architectural footprint. Pathways utilize swept, heat-bent configurations to ensure clean, low-friction CAT6 wire pulls.

Description	Estimated Qty	Unit	Unit Price (PHP)(With 30% Markup)	Total Price (PHP)
CAT6 UTP Data Cable (305m / Box)	2	boxes	₱11,700.00	₱23,400.00
1/2" (20mm) Thick-Walled PVC Conduit Pipes • Standard 3-meter length (10 ft)	55	pcs	₱115.00	₱6,325.00
1/2" PVC Flexible Corrugated Conduit Hose • For neat, adjustable ceiling-to-camera protection runs	1	roll	₱1,150.00	₱1,150.00
Decorative PVC Wall Moldings (1-inch) • For clean surface cable	15	pcs	₱160.00	₱2,400.00

Description	Estimated Qty	Unit	Unit Price (PHP)(With 30% Markup)	Total Price (PHP)
management in exposed office areas				
PVC Deep Junction Boxes (Heavy-duty camera weather bases)	16	pcs	₱260.00	₱4,160.00
1/2" PVC Male Adapters & Locknuts • Secures conduit lines firmly into junctions	32	pcs	₱15.00	₱480.00
PVC Pipe Solvent Cement (Glue) (400cc can)	2	cans	₱260.00	₱520.00
Metal Conduit Pipe Clamps & Heavy Screws/Tox	2	packs	₱450.00	₱900.00
Pass-Through RJ45 Connectors (High-grade CAT6)	50	pcs	₱15.60	₱780.00
Strain Relief RJ45 Rubber Boots	50	pcs	₱15.60	₱780.00
Heavy-Duty Plastic Cable Ties (Zip Ties) (8-inch length)	3	packs	₱170.00	₱510.00
1/2" PVC Elbows (90-Degree) • Only used for tight structural corners where sweeping bends cannot fit	10	pcs	₱20.00	₱200.00
SUBTOTAL — CABLING & CONTAINMENT				₱42,605.00

III. TECHNICAL SERVICES, MOBILIZATION & INSTALLATION

Covers technical labor, structural framing, swept conduit pathway bending, high-grade termination, custom NVR platform programming, and mobile app deployment. Tool procurement is factored directly into this section.

Description	Qty	Unit	Unit Price (PHP)	Total Price (PHP)
Mobilization, Tooling, Installation, Programming & Professional Labor Fees <i>(Billed at a flat rate per physical endpoint node)</i>	16	Nodes	₱10,875.00	₱174,000.00
SUBTOTAL — TECHNICAL SERVICES & LABOR				₱174,000.00

TOTAL CONTRACT PRICE: ₱413,425.00

PROJECT NOTES & ENGINEERING CLAUSES

1. Warranty & Service Deliverables

- **Hardware Warranty:** All core Dahua components (NVR, Cameras, PoE Switch) carry a **One (1) Year Local Warranty** covering factory defects. Any components found defective under normal operating conditions will be replaced or repaired at no charge.
- **Exclusions:** The warranty strictly excludes hardware damage resulting from incoming power surges, lightning strikes, localized building flooding, or unauthorized client tampering/reconfiguration.
- **Service Aftercare:** Includes **30 days of complimentary on-site technical support** starting from the official date of project turnover. Any service calls or physical site adjustments requested beyond this 30-day window will incur a standard technician mobilization fee.

2. Implementation & Aesthetic Standards

- **Conduit Integrity:** To ensure maximum wire life and minimize signal drag over the upgraded CAT6 infrastructure, structural routing will prioritize **continuous, cold-bent swept profiles using a professional internal bending spring** rather than rigid segmented joints. This limits cable snags and prevents moisture pooling points.
- **Enclosure Security:** The centralized head-end hardware (NVR, PoE Switch, and UPS) will be securely enclosed within a lockable, wall-mounted 6U server cabinet located in the designated **"DVR/MONITOR"** room to restrict physical data access to authorized personnel only.

3. Client Prerequisites & Infrastructure Responsibilities

- **Power Provisioning:** The client shall ensure a dedicated, active 220V AC electrical convenience outlet is installed adjacent to the specified server cabinet mounting location prior to technical mobilization.
- **Network Integration:** To enable remote mobile camera viewing on smartphones or laptops via the cloud framework, the client must provision an active internet connection (router/modem with an open LAN gateway port) within the DVR/Monitor room.
- **Structural Access:** The client shall grant full, unhindered access to all interior rooms, corridors, and ceiling spaces during the installation window, and assist in securing necessary internal building or management clearances.

4. Commercial Validity

- This cost estimate remains firm and valid for a period of **thirty (30) days** from the date of submission. Any modifications to the 16-camera layout drawn on the architectural blueprint will require a mutually signed Change Order before work commences.